9. The rates are to be entered both in figures and words.
10. Rates once tendered will on no account be increased afterwards.
11. Tenders stating that the dues in the Department may be adjusted towards the earnest money will be rejected.

Abstract estimate for Raising the Capacity of Brahmanahally Tank, Reg. No. 2 of Gudibanda Sub-Taluk.

No.	Items of work	Unit	Rate Rs. a. p.	Quantity	Cost
	BUND.				
1	Cutting removing jungle with roots	Grades		9	
2	Cutting grips to bund	..		9	
3	Earthwork to bund with watering and tamping ..	C.yds.		6256	
3(*a*)	Lead for conveying earth got out of draft clearing	..		115	
4	Removing and refixing old grade stones ..	Each		10	
5	Providing new top width stones	,,		10	
6	Providing date and new Reg. No. Stone with cutting figures, painting, etc., complete ..	,,		1	
7	Do Gauge Stone	,,		1	
8	Do B. M. Stones	,,		2	
9	Constructing new rough stone revetment ..	C.yds.		355	
10	Resetting old stone revetment with new jelly, etc., complete	,,		50	
	SLUICE.				
1	Earthwork excavation	C.yds.		8	
2	Size stone in Surki Mortar	C.ft.		463½	
3	Concrete in Surki Mortar	,,		20¼	
4	Providing Burnt Stone Slabs, dressed	..		42	
5	Pointing with Surki Mortar	Sqr.		351	
	Pointing with cement	,,		25	
	WASTE WEIR.				
1	Excavating in chuttu Soil	C.yds.		114	
1(*a*)	Do in gravelly Soil	,,		115	
2	Dismantling Masonry	C.ft.		434	
3	Benching rock 3″ to 6″	S.ft.		68	
3(*a*)	Surki Concrete including ramp	C.ft.		188	
4	Size Stone in Surki Mortar	,,		307	
5	Providing burnt stone slabs 6″ thick	S.ft.		117	
6	Constructing Burnt Stone revetment	C.yds.		12	
7	Pointing with Surki Mortar	Sqr.		5.06	
8	Providing Joggle joints in Slabs	Each		12	

P. SUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 21st August 1934.

The attention of the Public is hereby invited to the advertisement in pages 1114-1115 of the *Mysore Gazette*, calling for tenders for constructing a combined Dispensary for Men and Women at Nanjangud.

V. V. PATANKAR,
Executive Engineer.